#### Wedotanks.com Systems, LLC

PRECAST CONCRETE TANKS
For
Wastewater Treatment Systems

### Pouring base slab


Sloped Floors
Individual compartments
Virtually no limit to size





#### Keyway Forms for sloped floor

Bottom of keyway form is laid level-sides are sloped



#### **Erecting Precast**

Panels are delivered to site by truck or they can be poured right on site

A crane sits on slab & lifts panels into place





#### **Joint Sealing**


After erection complete, joint sealing procedure implemented.

- 1. Hydraulic cement is applied to joints inside and outside of tank.
- 2. A 3" -4" strip is applied over the joint once grout is set up.
- 3. CIM 1000 is injected into the joint at bottom of panel until it comes out at top of panel.

#### Joint Sealing Cont.


Procedure & Special Pump





Design & Engineering by Wedotanks.com Systems, LLC

# Joint Sealing Cont. Typical Core samples for piping through tank walls



#### **EXTERIOR FINISH**

Plain finish



Decorative finish



#### WATER TESTING

Each compartment is water tested to approximately one (1) foot below the top of the panel. Adjacent compartments are empty.

Tanks are tested with no backfill around the outside.

Once testing is completed, tanks are drained, backfilling to desired level can be completed and tank(s) are ready for service.


#### **Extended Aeration WWTP**



- ✓ Decorative Exterior Finish
- ✓ Catwalks and railings around each tank
- ✓ Air lift pumps for efficient pumping
- ✓ All equipment accessible for catwalks
- ✓ Hoist provided to lift heavier equipment
- ✓ Complete redundancy built in



#### SBR with Tertiary Filters



# SBR with BNR (Biological Nutrient Removal)



- ✓ All equipment accessible for top of tank
- ✓ Equipment plugs for ease of changing pumps & other equipment

3/27/2014 Systems, LLC

12

#### Expansion made easy to existing plants

- ✓ Simply add 3 sides to existing plant-(We design this into our plants)
- ✓ Existing plant remains in complete operation during expansion process
  - > 30K/day addition to existing 60K Extended Aeration Plant-New capacity is 90,000 Gal/Day.
  - Also added sodium hyprochlorite addition for disinfection



### Expansion made easy

#### Expansion to existing Tank Systems

Our precast concrete tank system is easily expandable, simply by adding three (3) additional sides to any of our tank systems. An example of a recent expansion is shown below.

**During original construction** extended footings are added on the side to be expanded. Base slab and footings for new addition are added while the existing plant remains in operation. Completed plant is ready for service This was a 30,000 GPD addition to an existing 60,000 GPD plant

Design & Engineering by Wedotanks.com Systems, LLC

### Precast Concrete or Castin-Place – We do both



#### Harbor Beach-3.0MG CSO

(Combined Sewer Overflow w/built in lift station)









#### AUBURN, IN

### 3.0 MG CSO with direct outfall w/disinfection









Design & Engineering by Wedotanks.com-Systems, LLC

# Water tank with pumping system. Ideal for irrigating golf course, potable water storage & reserve fire protection.




### Advantages of our system

- ✓ Our team of experienced professionals will provide long term sustainable solutions for your Water and Wastewater needs.
- ✓ Compact design.
- Less site invasiveness and more land for development.
- ✓ Permitting through Startup for a complete and compact system.

## A typical 750,000 GPD that is already permitted in the US.

- ✓ Extended Aeration
- ✓ Biological Nutrient Removal (BNR)
- ✓ Grit Removal
- ✓ Equalization
- ✓ Biosolids Storage
- ✓ Control Building
- ✓ Tertiary Filters
- ✓ U-V Disinfection

# Simulations are run on all designs with our unique simulation software to assure the design will meet effluent requirements



#### 750,000 GPD Layout

